Guideline Statement

Purpose

Keyword	Code	Document name	Docu ment Location
Induction	HS805	Contractor induction checklist	http://safety.unsw.edu.au/documents-resources
Report	HS809	HS Performance report for Contractors	http://safety.unsw.edu.au/documents-resources
Policy	-	UNSW Health and Safety Policy	http://safety.unsw.edu.au/documents-resources
Policy	-	UNSW Environmental Policy	http://safety.unsw.edu.au/documents-resources
Asbestos	FMHS-AS01	UNSW Asbestos Management Plan | Work Health & Safety	
Asbestos	FMHS-AS02	Asbestos Fact Sheet	www.contractorsafety.unsw.edu.au - documents
Asbestos	HS918	Asbestos Work Permit	
Access	FMHS-CTR04a	Construction Contractor access authorisation form	

5. UNSW Environmental Policy

All contractors must be familiar with the UNSW Environmental policy statement: https://safety.unsw.edu.au/

6. UNSW Contractor Online Safety Management System

All businesses and individuals must register in the system as per the process steps below.

6.1.

6.2. Individual contractor registration

The following steps outline how individual contractors access to the online contractor system.

STEP 1	Go to the following link: www.contractorsafety.unsw.edu.au
STEP 2	Select the contractor login/register option
STEP 3	Search for the company you are working under on the UNSW site.

6.3. Contractor system queries

For any comments contact the following:

- contractorsafety@unsw.edu.au or

8. Contractor Safety Documentation

Depending on the work being performed, contractors will need to supply the following safety documents to their UNSW Project Manager.

Construction Projects
Plan - Construction site safety plan[1] (mandatory) Plan - Environmental management plan[2] (mandatory) Plan - Construction traffic management plan[3] (mandatory) Insurance - Public liability insurance (mandatory) Insurance - Workers' compensation insurance[4] (mandatory) Insurance - Professional indemnity insurance[5] Insurance - Product liability insurance[6] Safety in design - documents[7] Certification - Safety standard certification (ISO 450001, 4801 or 18001)[8] Certification - Environment standard certification (ISO 14001)[9] Certification - Quality certification (ISO 9001)[10] Asbestos - Asbestos removal insurance[11] Report – UNSW HS809 Monthly safety report needs to be completed for projects going for longer than 1 month (mandatory)
Major Service Contracts *(cleaning, asset maintenance etc)*
Plan - Site safety plan[1] (mandatory) Plan - Environmental management plan Insurance - Public liability insurance (mandatory) Insurance - Workers' compensation insurance[4] (mandatory) Insurance - Professional indemnity insurance [5] Insurance - Product liability insurance [6] Safety in design - Safety in design documents [7] Certification - Safety standard certification (ISO 450001, 4801 or 18001) [8] Certification - Environment standard certification (ISO 14001) [9] Certification - Quality certification (ISO 9001)[10] Asbestos - Asbestos removal insurance [11]

adc6246d24 2 50.003 T5 (on)6 0 Td [(C)-jSva50.000 Tdn dH[(1)48 27.5 (on80915 Td <0089>Tj 3.0<</MC (c) 1 Tf CS0

9. Inductions for the UNSW site

All contractors must undertake the following inductions where applicable, the information below is also listed within the various relevant topic areas via the online portal.

Inducti nnduc e

Step 2

    - Report any WHS hazards and incidents to the project manager
    - Take part in WHS consultative arrangements
- Records & documents
    - Maintain all WHS records as required
    - Have all safety documents available on site
- Emergency Management
    - Follow Emergency and Evacuation procedures

18.2. Commitment to Environmental Protection

Contractors working on the UNSW site must ensure the following (not strictly exhaustive):

- Reasonable Care
    - Take all reasonable steps to ensure their work does not adversely impact the environment
- Controls
    - Ensure that all necessary pollution control measures are in place and are regularly checked and maintained to minimise risk of environmental incidents
- Fines
    - Individuals can be fined substantial amounts and may face imprisonment for seriously polluting the environment. While smaller incidents of environmental pollution can incur fines of up to $1,500, corporations may be fined up to $5M and/or 7 years' jail.
- Policy
    - UNSW also has an Environmental policy that states its commitment to protection of the Environment : UNSW Environment Policy
    - http://safety.unsw.edu.au/documents-resources

19. Safety Compliance

19.1. Risk Management

For general risk management, UNSW requires all contractors to implement risk control methodology as set out under national and UNSW risk management codes and procedures:

- Code of practise: How to manage work health and safety risks
- HS329 Risk Management Procedure – http://safety.unsw.edu.au/documents-resources

19.2. Hazards and Incidents

- Hazard
    - A hazard is a situation or thing that has the pot2.

19.3. Audits and Inspections

UNSW Reserves the right undertake audits and inspections of any contractor documents and worksites. In doing so, the following things will generally be checked:

- Documents: contractors where requested are required to provide any safety documents for review
- Feedback: feedback will be provided to contractors for any audits or inspection activities conducted
- Rude or abusive behaviour: to any of the UNSW safety team doing inspections will not be tolerated. Any contractor doing so will be listed in the UNSW incident register.

19.4. UNSW Safety Signage

- Safety signs are placed on UNSW campuses and property to protect health and safety.
- Safety signs of different colours and shapes mean different things, for further information see the tables below or consult the following document: HS732 Signage Guideline

PPE charts

UNSW Emergency chart

19.5. Safe Work Method Statements (SWMS)

A SWMS or JSA must be developed for any hazardous or high-risk or work on the UNSW site. All SWMS must meet compliance requirements against the UNSW HS811 checklist.

Examples of work requiring SWMS include (not strictly exhaustive):

Hazardous Work - *WHS Reg. 2017: CH4*	Major hazard categories
• Demolition work	• Hazardous chemicals - *WHS Reg. 2017: CH7*
• General electrical safety in workplaces and energised electrical work	• Asbestos- *WHS Reg. 2017: CH8*
• Falls	• Plant and equipment risks- *WHS Reg. 2017: CH5*
• Confined spaces	
• Manual tasks (hazardous)	
• Noise	
• Diving work	
• Falling objects	
• Work generating airborne contaminants	
• Hazardous atmospheres	
• Storage of flammable or combustible substances	
• Remote or isolated work	
• Hazardous building materials (asbestos, lead & other)	
High Risk Work - *WHS Reg. 2017: Schedule 3*	
• Scaffolding work	• Boom-type elevating work platform
• Dogging and Rigging work	• Concrete placing boom
• Crane and hoist operation	• Reach stackers
• Materials hoist	• Forklift operation
• Personnel and materials hoist	• Pressure equipment operation
High Risk Construction work - *WHS Reg. 2017: CH6*	
• Falls risk (>2m)	• Electrical services (live)
• telecommunication tower work	• Flammable (atmosphere)
• Demolition	• Concrete (pre-cast etc)
• Asbestos removal	• Traffic risks
• Collapse	• Mobile Plant
• Confined space entry	• Temperature (extremes)
• Shaft or trench work (>1.5m)	• Water (drowning risk)
• Explosives	• Diving work
• Pressure risks	
• Chemical (lines)	

UNSW recognises that controls for different jobs of the same nature may not drastically change, however the specific nature of the project or work will change, and this must be reflected in each SWMS.

19.6. Licenses and Competencies

Relevant licenses and competencies for work must be:

- documented in risk control documents (i.e., SWMS)
- available to UNSW Project Manager in the online portal

If a license or competency cannot be produced or has expired, then work will be ordered to stop until the issue is resolved.

19.7. Housekeeping

Contractors must ensure all work areas and associated surround.4 d ainurkanotsu/ Td [(H0.5 a -1.6231.5 ( )0m)-2 (t)3n.5 (

19.9. Personal Protective Equipment (PPE)

PPE is an important of part risk control methodology, contractors need to observe the following PPE requirements.

- Supply: contractors are required to bring their own PPE on site
- Suitability: PPE must be suited for the job, meet current compliance and not be in a state of disrepair
- Further information: refer to the following guide on the UNSW Safety Website: HS659 Personal Protective Equipment Guideline

- Lab-based PPE: in some cases, UNSW will provide PPE where there is a specialist requirement for an environment i.e.,

Parking DO's

- Speed limits: the speed limit is 10km/hr and pedestrians always have right of way at UNSW campuses and properties.
- Stick to the road : parking or driving across footpaths and grassed or landscaped areas is prohibited. Where the nature of works requires a vehicle to be driven on these areas, permission must be obtained through your UNSW Project Manager. Once permission has been obtained, you must ensure the following:
    - Have a spotter on foot direct you in areas of high pedestrian usage or recreation
    - Make sure that it is safe to drive across the footpath, grassed or landscaped area
- Barriers: place barriers around the vehicle and work area, and
- Authorised parking: park only in designated areas such as loading zones, permit bays or areas which have been approved by UNSW Security

Parking DONTS - X

- Block access ways : illegally park/ block roads or foot paths
- Lawns/ gardens: park on lawns or garden beds (unless approved)
- Phones: at no time must you drive and use a mobile phone in an illegal manner, for further information see the following:

http://roadsafety.transport.nsw.gov.au/stayingsafe/mobilephones/know-the-rules.html

- Parking on Slopes
    - Contractors must not park on slopes
    - If there is a critical need to park on slopes, then special written permission must be granted by the UNSW Project Manager. Controls such as wheel chocks, parking in gear, turning wheels 45 degrees will need to be used and documented in the relevant SWMS

Example of wheel chocks

Illegal parking on a slope at UNSW

**NOTE - Fatal vehicle pedestrian/vehicle conflict incidents have occurred in the past on site. Any